

MODEL : PS-05-24

OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	RIPPLE & NOISE	V1: 200 mVp-p (Max)	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	V1: 16 mVp-p	P
2	OUTPUT VOLTAGE TOLERANCE	V1: 2 %~ -2% (Max)	I/P: 85 VAC / 264 VAC O/P:FULL/ 0% LOAD Ta:25°C	V1: 0.03%~ 0%	P
3	LINE REGULATION	V1: 1 %~ -1% (Max)	I/P: 85 VAC ~ 264VAC O/P:FULL LOAD Ta:25°C	V1: 0%~ 0%	P
4	LOAD REGULATION	V1: 1 %~ -1% (Max)	I/P: 230 VAC O/P:FULL -MIN LOAD Ta:25°C	V1: 0%~ 0%	P
5	SET UP TIME	230VAC/1000 ms (Max)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	230 VAC/796 ms	P
6	RISE TIME	230VAC/ 20 ms (Max)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	230 VAC/ 11 ms	P
7	HOLD UP TIME	230VAC/ 100 ms (TYP)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	230VAC/ 173 ms	P
8	OVER/UNDERSHOOT TEST	< ±5%	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	TEST: <5 %	P
9	DYNAMIC LOAD	V1: 2400 mVp-p	I/P: 230 VAC O/P:FULL /Min LOAD 90%DUTY/1KHZ Ta:25°C	163 mVp-p	P

**INPUT FUNCTION TEST**

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDICT
1	INPUT VOLTAGE RANGE	85 VAC~ 264 VAC	I/P:TESTING O/P:FULL LOAD Ta:25°C	45.9 VAC~ 264 VAC	P
			I/P: LOW-LINE-3V=87 V HIGH-LINE+15%= 300 V O/P:FULL/MIN LOAD ON: 30 Sec . OFF: 30 Sec 10MIN ( AC POWER ON/OFF NO DAMAGE )	TEST: OK	
2	INPUT FREQUENCY RANGE	47HZ ~63 HZ NO DAMAGE OSC	I/P: 85 VAC ~264 VAC O/P:FULL-MIN LOAD Ta:25°C	TEST: OK	P
3	EFFICIENCY	76% (TYP)	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	76.626%	P
4	INPUT CURRENT	230 V/ 0.07 A (TYP) 115 V/ 0.15 A (TYP)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	I =0.0683 A/ 230VAC I =0.104 A/ 115VAC	P
5	INRUSH CURRENT	230 V/ 30 A (Max) COLD START	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	I = 19.437 A/ 230VAC	P
6	LEAKAGE CURRENT	< 0.5 mA / 240VAC	I/P: 254 VAC O/P:Min LOAD Ta:25°C	L-FG: 0.18 mA N-FG: 0.18 mA	P

**PROTECTION FUNCTION TEST**

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDICT
1	OVER LOAD PROTECTION	above 105%	I/P: 230 VAC I/P: 115 VAC O/P:TESTING Ta:25°C	305 %/ 230VAC 235 %/ 115VAC Hiccup Mode	P
2	OVER VOLTAGE PROTECTION	CH1: 27.6 V~ 32.4 V	I/P: 230 VAC O/P:MIN LOAD Ta:25°C	28V	P
3	OVER TEMPERATURE PROTECTION	SPEC: Tj 140 typically (U1) Detect on main control IC	I/P: 230 VAC O/P:FULL LOAD	O.T.P. Active Hiccup mode ,recovery automatically after fault condition is removed	P
4	SHORT PROTECTION	SHORT EVERY OUTPUT 1 HOUR NO DAMAGE	I/P: 264 VAC O/P: FULL LOAD Ta:25°C	NO DAMAGE Hiccup Mode	P

**ENVIRONMENT TEST**

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	TEMPERATURE RISE TEST	MODEL : PS-05-24 1. ROOM AMBIENT BURN-IN : 1HRS I/P: 230 VAC O/P: 100% LOAD Ta= 28.9 °C 2. HIGH AMBIENT BURN-IN : 3HRS I/P: 230 VAC O/P: 100% LOAD Ta= 51.3 °C			P
2	OVER LOAD BURN-IN TEST	NO DAMAGE 1 HOUR ( MIN )	I/P: 230VAC O/P: 120% LOAD Ta:25°C	TEST : OK	P
3	LOW TEMPERATURE TURN ON TEST	TURN ON AFTER 2 HOUR	I/P: 230 VAC O/P: 100 % LOAD Ta= -10°C	TEST : OK	P
4	HIGH HUMIDITY HIGH TEMPERATURE HIGH VOLTAGE TURN ON TEST	AFTER 12 HOURS IN CHAMBER ON CONTROL 50 °C NO DAMAGE	I/P: 272 VAC O/P:FULL LOAD Ta= 50°C HUMIDITY= 95 %R.H	TEST : OK	P
5	TEMPERATURE COEFFICIENT	± 0.05 %(0-50°C)	I/P: 230 VAC O/P:FULL LOAD	± 0.02 %(0-50°C)	P
6	VIBRATION TEST	1 Carton & 1 Set Operating at I/P: (1) Waveform: Sine Wave (2) Frequency:10-500Hz (3) Sweep Time:10min/sweep cycle (4) Acceleration:2G (5) Test Time:1 hour in each axis (X.Y.Z) (6) Ta:25°C	VAC NO LOAD	TEST : OK	P

**SAFETY TEST**

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	WITHSTAND VOLTAGE	I/P-O/P: 3 KVAC/min	I/P-O/P: 3 KVAC/min Ta:25°C	I/P-O/P: 1.3 mA NO DAMAGE	P
2	ISOLATION RESISTANCE	I/P-O/P:500VDC>100MΩ	I/P-O/P: 500 VDC Ta:25°C	I/P-O/P: 24.9G Ω NO DAMAGE	P
3	GROUNDING CONTINUITY	FG(PE) TO CHASSIS OR TRACE < 100 mΩ	40A / 2min Ta:25°C	6 mΩ	P



## E.M.C TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	HARMONIC	EN61000-3-2 CLASS A	I/P: 230 VAC/50HZ O/P: FULL LOAD Ta: 25°C	PASS	P

## M.T.B.F &amp; LIFE CYCLE CALCULATION

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	CAPACITOR LIFE CYCLE	PS-05-24: SUPPOSE C11 IS THE MOST CRITICAL COMPONENT I/P : 230VAC O/P : FULL LOAD Ta= 25 °C LIFE TIME= 331538 HRS I/P : 230 VAC O/P : FULL LOAD Ta=50 °C LIFE TIME= 98571 HRS			P

DATE	SAMPLE	TEST RESULT	TESTER	APPROVAL
2004/12/24	RD SAMPLE	PASS	SANFORD SU	VINCENT TSENG

2005/09/10 A40-G022